



कृषि मंत्रालय (कृषि अनुसंधान एवं शिक्षा विभाग), भारत सरकार  
भाकृअनुप - केन्द्रीय तटीय कृषि अनुसंधान संस्थान  
भारतीय कृषि अनुसंधान परिषद  
एला, ओल्ड गोवा - 403 402 (भारत)

Ministry of Agriculture (Department of Agricultural Research and Education), GOVERNMENT OF INDIA

**ICAR- CENTRAL COASTAL AGRICULTURAL RESEARCH INSTITUTE**

Indian Council of Agricultural Research

Ela, Old Goa - 403 402 (INDIA)



Registered AD

F. No. 4(347)/Repair of Pig drain/Block B/Works/17-18 -5122

Date: 27.01.2018

To,  
ARIS cell

**Sub:- Inviting quotation for Repair of the piggery drain near Piglet Unit in Block B - reg.**

Sir,

Sealed quotations for execution of works as per the specifications given in the abstract attached are invited by the Director, ICAR – Central Coastal Agricultural Research Institute, Ela, Old Goa from the contractors so as to reach this Office on or before **17-02-2018 by 3.00 p.m.** The sealed cover containing the quotation should be superscribed as **“quotation for Repair of the piggery drain near Piglet Unit in Block B at ICAR- CCARI, Ela Old Goa under Institute due on 17-02-2018 vide reference No. 4(347)/Repair of Pig drain/Block B/Works/17-18 dated 27-01-2018**

Abstract Attached

P.T.O



हर कदम, हर डगर  
किसानों का हमसफर  
भारतीय कृषि अनुसंधान परिषद

*Agrisearch with a human touch*



एक कदम स्वच्छता की ओर

\* Ph : 0832-2284678 / 79 / 2285381, 0832-2285448 (AO)

\* Fax : 0832-2285649

\* E-mail : director.ccari@icar.gov.in

\* Website : <http://icargoa.res.in>

1. The rate for the work should be quoted as per GSR & Labour Cess as applicable against each description of work and should indicate the total of each description work and Grand Total, failing which the quotation will be rejected.
2. Rates quoted should be inclusive of incidental charges including all the applicable legal charges. GST, wherever applicable, should be shown separately.
3. The quotation should be dropped in the Quotation Box kept for the purpose at this Institute.
4. The quotation will be opened by the Works Committee constituted for the purpose at ICAR – CCARI, Ela Old, Goa on **19.02.2018 at 3.00 pm** in the presence of tenderers, if any.
5. The quotation should be accompanied by a Demand Draft of **Rs. 3500/-** (Rupees Three Thousand Five Hundred only) ~~each work~~ as Earnest Money Deposit (EMD) by way of Crossed Demand drawn in favour of ICAR Unit, ICAR – CCARI, Ela Old Goa, which may be recorded on the sealed cover that EMD for **Rs.3500/-** is enclosed.
6. The EMD will be returned to the UNSUCCESSFUL tenderers, after finalization of the quotation, for which application for refund of EMD and pre-receipt should be enclosed along with the quotation.
7. Successful tenderers have to deposit Security Money @ 10% of the total cost of the work involved in deal before starting the work for the period of contract towards proper performance of contract which will be released after one year of successful completion of works and which will be treated as guarantee for successful performance of completed works.
8. No farm implements will be provided from this Office to the Contractors for the work.
9. Payment will be made by mode of e- payment in favour of the Contractor/party after completion of the work satisfactorily and on production of your pre-receipted bill. **The following details may be intimated i) Account holder's name ii) type of account and account no. iii) Name of bank and address. iv) RTGs code no, of bank. V) IFSC No. of bank & MICR Code.**
10. The quotation should be signed by the Contractor/Party with name and full address and the quotation received without the same will not be accepted.
11. The PAN No. along with a photo copy of the PAN Card of the Contractor should be enclosed along with the quotation. Without the same, the quotation will not be entertained and will be rejected.
12. For clarification if any, Smt. Madina Solapuri, Estate Officer at ICAR- CCARI, may be contacted.
13. The right to accept or reject any or all quotations without assigning any reason is reserved by the Director, ICAR - CCARI, Old Goa.

  
29/01/18  
Administrative Officer

Sr.No 1	Description of Work 2	Unit 3	Quantity 4	Rate 5	Amount 6
1	Earthwork in excavation in foundation pipeline trenches, drain in saturated soil upto a depth of 0.60 Mt. Lift upto 1.50 Mt. Including shoring, strutting and pumping/bailing out water stacking the excavated soil not more than 5m. Clear from the edge the excavation and returning the stacked soil in 0.15m layers when required into plinth sides of foundation etc. consolidating each deposited layer by ramming, watering and disposing of all surplus excavated soil within a lead upto 20m.	Cu.m	24.000		
2	Rubble packing with hard laterite stone under floors including watering ramming and consolidating etc. in pipeline trenches and other foundation complete.	Cu.m	4.000		
3	Providing and laying cement concrete 1:3:6 (1 cement : 3 coarse sand :6 graded granitic or basaltic stone aggregate 40m nominal size) excluding cost of cantering and shuttering and finishing in a)All works upto plinth level	Cu.m	3.000		
4	Providing and laying in position (1:11/2:3) Reinforced cement concrete excluding the cost of centring, shutters, finishing and reinforcement ( 1 cement : 1 Coarse sand : 3 graded stone agg 20mm nominal size) ii) in wall (any thickness),including attached pilasters, buttresses, pinth and string courses, fillets, columns, pillars, pipers, abutment, posts and struts etc. upto floor five level	Cu.m	4.090		
5	Providing TMT steel reinforcement (Confirming to IS 1786 of 1986) for RCC including bending, binding & placing in position in all the floor along with the factory made precast concrete cover block of specified sizes whose compressive strength is not less than that of surrounding concrete in the structural member	kg	500.00		

Sr.No	Description of work	Unit 3	Quantity 4	Rate 5	Amount 6
6	Cantering & shuttering including Strutting Propping & removal of form for ii)Vertical surface such as retaining walls, return walls, Partition, walls( any thickness) including attached Pilasters, Buttresses, Plinth and string course, Fillets and the like	Sq.m	32.00		
7	Neatly cement punning	Sq.m	24.000		
8	18 mm cement plaster in two coats under layer 12mm thick cement plaster 1:5 (1 cement : 5 coarse sand) and top layer 6 mm thick with cement plaster 1:3 ( 1 cement : 3 coarse sand) finished with sponge.	Sq.m	24.000		
9	Supplying & fixing of Factory made Precast RCC slab at site in concrete Grade of M25 with 20 mm nominal size Granitic or basaltic aggregate, consolidated by means of mechanical platform, vibration etc. with lift hooks of MS 10mm bars & PVC cup including cost of reinforcement etc. complete and directed by the Engineer-in-charge f) size 1200x 400 x 150 mm with reinforcement not less than 9 kg	Sq.m	20.000		
<b>Total</b>					