



**भाकृअनुप - केन्द्रीय तटीय कृषि अनुसंधान संस्थान**

भारतीय कृषि अनुसंधान परिषद

एला, ओल्ड गोवा - 403 402 (भारत)

Ministry of Agriculture (Department of Agricultural Research and Education), GOVERNMENT OF INDIA

**ICAR- CENTRAL COASTAL AGRICULTURAL RESEARCH INSTITUTE**

*Indian Council of Agricultural Research*

Ela, Old Goa - 403 402 (INDIA)

F. No. 4(211)/Well-Block B/Paddy Field/2013-Works

Date: 29-06-2018

To,

Sub:- Inviting quotation for Repair & Maintenance of well near paddy field in Block- B at ICAR – CCARI, Old Goa - reg.

Sir,


Sealed quotations for execution of works as per the specifications given in the abstract attached are invited by the Director, ICAR – Central Coastal Agricultural Research Institute, Ela, Old Goa from the contractors so as to reach this Office on or before **21-07-2018 by 3.00 p.m.** The sealed cover containing the quotation should be superscribed as **“quotation for Repair & Maintenance of well near paddy field in Block- B at ICAR- CCARI, Ela Old Goa under Institute due on 21-07-2018 vide reference No. 4(211)/Well-Block B/Paddy Field/2013-Works dated 29-06-2018**

Abstract Attached

P.T.O

Terms & Conditions:

1. **The rate for the work should be quoted as per GSR & Labour Cess as applicable against each description of work as per "Annexure A" and should indicate the total of each description work and Grand Total, failing which the quotation will be rejected.**
2. **Rates quoted should be inclusive of incidental charges including all the applicable legal charges. GST, wherever applicable, should be shown separately.**
3. **The quotation should be dropped in the Quotation Box kept for the purpose at this Institute.**
4. The quotation will be opened by the **Committee for Tenders in Works** constituted for the purpose at ICAR – CCARI, Ela Old, Goa on **23-07-2018 at 3.00 pm** in the presence of tenderers, if any.
5. **Quotation should be accompanied with a Demand Draft of Rs. 1000/- drawn in favour of "ICAR Unit, ICAR – CCARI" payable at Old Goa as tender fee.**
6. The quotation should be accompanied with a Demand Draft of **Rs. 10,000/-** ( Rupees Ten Thousand only ) as Earnest Money Deposit (EMD) drawn in favour of ICAR Unit, ICAR – CCARI, payable at Goa, which may be recorded on the sealed cover that EMD for **Rs. 10,000/-** is enclosed.
7. **PWD licence/equivalent licence must be enclosed with the tender. Any tender without the necessary licence & EMD will not be considered.**
8. Successful tenderers have to deposit Security Money @ 10% of the total cost of the work involved in deal before starting the work for the period of contract towards proper performance of contract which will be released after one year of successful completion of works and which will be treated as guarantee for successful performance of completed works.
9. No farm implements will be provided from this Office to the Contractors for the work.
10. Payment will be made by mode of e- payment in favour of the Contractor/party after completion of the work satisfactorily and on production of your pre-receipted bill. **The following details may be intimated i) Account holder's name ii) type of account and account no. iii) Name of bank and address. iv) RTGs code no, of bank. v) IFSC No. of bank & MICR Code.**
11. The quotation should be signed by the Contractor/Party with name and full address and the quotation received without the same will not be accepted.
12. The contractor shall indemnify and keep indemnified the ICAR - CCARI GOA from any claims, loss or damages that may be caused to it on account of any failure to comply with the obligations under various laws of Central or State. In case of any dispute, the decision of the Director, ICAR-CCARI Goa shall be final and binding on the contractor.
13. **The PAN No. along with a photo copy of the PAN Card of the Contractor and the photo copy of registration as Contractor in Goa-PWD should be enclosed along with the quotation. Without the same, the quotation will not be considered .**
14. For clarification if any, Smt. Madina Sollapuri, Estate Officer at ICAR- CCARI, may be contacted.
15. The right to accept or reject any or all quotations without assigning any reason is reserved by the Director, ICAR - CCARI, Old Goa.

  
 29/06/18  
 Administrative Officer

Name of the work:-Repair and Maintenance of well near paddy field in block B

Page No.1

**Estimated Cost: Rs. 4,99,667.00**

Sr.No 1	Description of work 2	Unit 3	Quantity 4	Rate 5	Amount 6
1	Repair to plaster in patches of 2.5 sq.m and under including cutting the patch in proper shape and preparing and plastering the surface of the wall complete including disposal of rubbish to the dumping ground within 50m lead with cement mortar 1:4 (1 cement : 4 fine sand)	Sq.m	104.00		
2	Demolishing laterite stone masonry in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 mts. lead	Cu.m	56.420		
3	Clearing grass and removal of rubbish upto a distance of 50 m outside the periphery of the area	Sq.m	225.000		
4	Earthwork in excavation over area in saturated soil (exceeding 0.30 M upto a depth of 0.60 M including disposal of excavated earth lead upto 50 M and lift upto 1.5 M disposed earth to be neatly dressed and levelled including pumping or bailing out water.	Cu.m	143.360		
5	Extra for earthwork excavated in saturated soil for every 0.30 Mt. depth or part thereof over 0.60 m depth below water table including pumping and bailing out water	Cu.m	71.685		
6	Dewatering the trenches and bailing out water including removable of slush, mud etc. for any depth and disposal of pumped mud, water, slush to suitable point not forming circuit of return of pumped water to the very trench, by employing diesel generated pump	Cu.m	335.080		
7	Laterite masonry in neatly dressed stones of size as specified in cement mortar 1:5 (1 cement : 5 coarse sand) in foundation and basement.	Cu.m	56.420		
8	Providing and laying in position cement concrete 1:2:4 ( 1 cement : 2 stone coarse sand :4 graded granitic stone aggregate 40 m nominal size) excluding cost of cantering, shuttering and finished: a) All works upto plinth level	Cu.m	12.000		
9	Extra for laying concrete in or under water and or liquid mud including cost of pumping and bailing out water and removing slush etc. complete *Per cum per m depth.	*CPD	60.000		
10	Pointing on stone work with cement mortar 1:3 ( 1 cement : 3 fine sand) a) Flush pointing	Sq.m	144.000		
11	Removing white or colour wash by scrapping, sand papering and preparing surface smooth including necessary repair to scratches etc. complete.	Sq.m	108.000		
12	White washing with whiting on new work three or more coats to give an even shade.	Sq.m	108.000		
	TOTAL				